


SM10DCS

TNS

## versatile<sup>TM</sup> 4C Mailbox, 4CADD-4P



## COMPARTMENT CHART

## 1. This module meets the USPS STD-4C requirements for installation defined below when the mailbox is installed per the dimensions provided on this drawing.

- a. At least one customer compartment shall be positioned less then 48" above finished floor (AFF).
- b. No parcel locker (interior bottom shelf) shall be positioned less than 15" AFF.
- c. No patron (tenant) lock shall be positioned more than 67" AFF.
- d. No customer compartment (interior bottom shelf) shall be positioned less than 28" AFF.
- e. The USPS Arrow lock shall be positioned 36"- 48" AFF.
- 2. This 4C mailbox can also be used for private applications.

Notes:

3. The rough opening width for multi-unit 4C installations is provided using the Florence configurator: www.florencemailboxes.com/configurator.

|                  |                                   | DESCRIPTION | COMPARTMENT | COMPARTMENT SIZE      | QTY. |
|------------------|-----------------------------------|-------------|-------------|-----------------------|------|
|                  |                                   | PARCEL      | PL5         | 17" H x 12" W x 15" D | 4    |
| DDUDITOT SEDIES: | VEDCATHETM 4C EDONT LOAD AAAH DOV |             |             |                       |      |

MODEL 4CADD-4P REV SCALE NONE LAST REV DATE
DRAWING NUMBER DRAWN BY
4CADD-4PCS NBC